

Examples of Typical Mitigation Measures

TABLE J-1
Example of Typical Mitigation Measures

Environmental Concerns	Mitigation Measures	Application
WATER QUALITY Sedimentation of streams due to erosion from the right-of-way.	-minimize use of slopes adjacent to streams - maintain a cover crop.	During soil testing, selective cutting, construction and maintenance. During restoration following construction and long term maintenance.
Stream bank erosion.	- mechanical erosion control. - retain shrubby stream bank vegetation and selectively cut or prune trees. - selective spraying of herbicides.	In line clearing/maintenance. During line maintenance.
Impedance of natural flow of streams /-other surface waters.	- mechanical erosion control. - use and maintenance of appropriate stream crossing device. - use of equalizing culverts in roads in wetlands. - use of corduroy in wetlands, where available.	Stream crossings, as required. At stream crossings during construction and line operation. During construction and throughout line operation. Line construction in wetlands.
Ponding or channelization of surface waters due to rutting.	- timing activities to stable ground conditions. - use of gravel roads.	Construction/maintenance on seasonally unstable ground surfaces. New line construction on unstable ground surfaces.
Contamination of surface or ground waters through spills or leaks of toxic substances.	- spill control material and procedures readily available. - site selection where possible.	At station sites and in general whenever toxic substances are used. Stations warehousing sites and structures locations.
Sedimentation of streams with pumped soil/bentonite from dewatering operations.	- containment of material when working in the vicinity of water bodies. - use of sediment traps or settling tanks. - removal of material from the site.	Dewatering during installation of augured footings. When necessary during dewatering operation. Restoration.
Channel disturbance, sediment production at stream crossings.	- installation of an appropriate crossing device. - use of sediment traps or settling tanks.	During access road construction. During access road construction.
Increase in water temperature due to vegetation removal at stream crossings.	- retain shrubby stream bank vegetation and selectively cut/prune trees. - selective spraying of herbicides to retain as much vegetation as possible on stream banks.	Line clearing/maintenance. Line maintenance (vegetation control).
Reduction in water storage capacity due to removal of vegetation or diversion caused by rutting.	- selective removal of vegetation. - revegetation with compatible shrubs.	In identified source/recharge areas during initial line clearing. Selection of structure sites and access routes.

TABLE J-1(Continued)
Examples of Typical Migration Measures

Environmental Concerns	Mitigation Measures	Application
SOILS		
Soil compaction/topsoil-subsoil mixing.	- avoidance of rutting by vehicles. - construction timing. - use of gravel roads. - use of vehicles with low bearing pressure. - stop activities when ground conditions are poor.	Application in generally all phases of construction and maintenance, particularly during line clearing and construction. " " " "
Wind/water erosion.	- avoidance of areas with high erosion potential. - timing activities to the most stable ground conditions. - slope stabilization. - mechanical erosion control. - vegetation erosion control. - recompaction of trenches.	Access road location erodible soils, slopes. Access road location erodible soils, slopes. As required. As required. Erodible soils, slopes, as a restoration measure. Installation of counterpoise, underground transmission lines. Counterpoising on steep slopes. At station sites or during the transport of oil containing equipment. As an ongoing process.
Contamination by petro-chemicals.	- avoid trenching parallel to the fall of a slope. - spill control material and procedures made readily available. - restoration methods investigated.	At station sites or during the transport of oil containing equipment. As an ongoing process.
FISH AND WILDLIFE		
Loss of habitat, breeding and/or food source for terrestrial wildlife due to Vegetation removal.	- environmental mapping to identify sensitive sites. - avoidance of areas containing rare /- endangered species. - the creation of "edge" (may be considered a positive impact). - promotion of wildlife habitat through vegetation control and brush piles - avoid the filling of small wetlands.	Prior to the start of construction, line clearing Access road location, selective clearing for new lines. Selective clearing on a right-of-way. Restoration and right-of-way management. Access road and tower construction.
Changes in composition of vegetation as a result of soil disturbance.	- construction timing to minimize soil disturbance. - restoration of soils to a stable condition.	Right-of-way clearing and construction activities in general. Restoration following construction.
Removal or burial of stream bottom habitat and increased turbidity due to sedimentation.	- minimize erosion from the right-of-way by maintaining a cover crop. - mechanical erosion control. - minimize stream bank erosion by retaining shrubby bank vegetation and selective cutting/pruning of trees near watercourses. - installation of sediment traps when necessary. - containment or filtering of pumped spoil/water near watercourses.	Restoration and maintenance. As required during the operation of the line and maintenance of the right-of-way. At stream crossing during right-of-way clearing. At any time during construction as required During the installation of tower footings near watercourses.

TABLE J-1 (Continued)
Examples of Typical Mitigation Measures

Environmental Concerns	Mitigation Measures	Application
FISH AND WILDLIFE (con't)		
Impediment to the mitigation of fish or wildlife.	- avoid filling small wetlands serving as staging areas for waterfowl migration.	Small wetlands during access road and tower pad construction.
Impediment to the mitigation and/or breeding of fish or wildlife.	- installation and maintenance of proper stream crossing device. - time construction activities to avoid disturbance to migrating fish and wildlife or during breeding.	At stream crossings during construction and as required for maintenance. During construction and maintenance.
Change in the chemistry of water bodies.	- follow Ontario Hydro standards for the application of herbicides near watercourses. - minimize sedimentation of streams (see Water Quality). - prevent cut vegetation from entering watercourses. - selective spraying or manual control of vegetation near watercourses.	Near watercourses during line clearing and maintenance cycles. Near watercourses during line clearing, construction and throughout the operation of the line. Line clearing and maintenance cycles. Line clearing and maintenance cycles.
Increased water temperature as a result of clearing vegetation near streams.	- selective removal of vegetation; pruning. - retain shrubby bank vegetation.	At stream crossings during line clearing and maintenance cycles. At stream crossings during line clearing and maintenance cycles.
VEGETATION		
Introduction of exotic plant species resulting from vegetation erosion control.	- use of native species for erosion control.	On areas where erosion control is necessary.
Vegetation stress due to nutrient loss as a result of soil deterioration.	- erosion control measures.	The management of the right-of-way erosion prone slopes.
Changes in vegetation due to soil disturbance (topsoil-subsoil mixing).	- time construction/clearing to take advantage of stable soil conditions.	During construction and line clearing operations, maintenance cycles.
Loss of forested land	- hectare for hectare reforestation. - planting of wind breaks. - landscaping plantings.	Selection of clear cutting of transmission line right-of-way.
AGRICULTURE		
Loss of standing crop due to access road and tower work site.	- limit width of access and size of tower site. - monetary compensation for crop loss. - time construction to avoid growing season.	Agricultural areas - generally all construction/maintenance operations. Following determination of losses. Construction/maintenance.
Soil Compaction	- scheduling activities to times of the year when soils are least susceptible to compaction. - stop activities when ground conditions are poor. - use of equipment with low bearing capacity.	Construction/maintenance. Construction/maintenance. Construction/maintenance.

TABLE J-1 (Continued)
Esamples of Typical Mitigation Measures

Environmental Concerns	Mitigation Measures	Application
AGRICULTURE (Continued)		
Soil Compaction (cont'd)	- chisel ploughings - monetary compensation for subsequent crop reductions. - use of gravel roads. - locate access roads along existing traffic routes.	Restoration. Property settlements. Construction of new lines Construction/maintenance.
Topsoil-subsoil mixing/soil rutting.	- scheduling activities. - stop activity when ground conditions are poor. - use of equipment with low bearing capacity. - use of gravel roads. - backblading/grading. - addition of manures to offset fertility loss. - compensation for reduced soil productivity. - removal of soil and/or bentonite from foundation operations. - segregation of topsoil and subsoil.	Scheduling for construction/maintenance activities. Field decisions during construction phase of project. Construction/maintenance. Construction. Restoration. Restoration. As a result of negotiated settlement. Augured foundations.
Disturbance to Farm Operations.	- maintain contact with landowner/tenant regarding preferences.	Where required to prevent extensive mixing. Throughout construction and as maintenance work is required.
Damage to Field Tiles.	- avoidance of tile beds. - minimize tile crossings. - scheduling activities to times of the year when ground will support the equipment to be used. - use of soft track equipment. - protection of tile crossings by the placement of heavy steel plate. - stop activities when ground conditions are poor. - repair damaged drains. - compensate for damages.	Access road location landowner contact. Access road layout. All phases of construction/maintenance where the location of the tile drains is known. Construction/maintenance. Construction/maintenance. Field decision during construction phase of project. Restoration. As a result of negotiated settlement.
Loss of Livestock	- employ noise control measures near sensitive livestock. - construction of farm gates. - securing farm gates. - clean-up construction materials which could be ingested	During construction as required. Access road - construction. All activities. As an ongoing process throughout all phases of construction and maintenance.
SOCIETAL IMPACTS	- compensation for lost, injured livestock.	Following completion of construction, as a result of negotiations with claimant.
Noise and Vibration	- limit this type of work to daylight hours. - observe protocol or applicable municipal bylaws. - use of appropriate methods where available.	All phases of construction where high noise levels could be a problem, e.g. residential areas. All phases of construction where high noise levels could be a problem, e.g. residential areas. As required - special circumstances; e.g. hospitals.

TABLE J-1 (Continued)
Examples of Typical Mitigation Measures

Environmental Concerns	Mitigation Measures	Application
SOCIETAL IMPACTS		
Mud and Dust.	- wetting down dry soils. - chemical control of dust. - cleaning roads to remove mud. - temporary planting of grasses. - screen with natural or planted vegetation. - avoid linear access down the right-of-way. - addition of topsoil to gravel access roads. - hoarding construction sites. - installation of landscaping in advance of site completion.	All phases of construction. As required. As required. When the project duration permits and dust is a major problem, Access roads - right-of-way clearing; restoration. Access road location. Restoration of access roads. Station construction. Station construction.
Appearance - Lines.	- retain tree screens and curve access routes. - plant tree screens. - avoid sensitive soils for access routes. - stabilize erodible soils by vegetative or mechanical means. - add topsoil and seed gravel access routes.	Where appropriate vegetation exists. Where appropriate. Where possible. Where soils are subject to erosion. Where exposed to public view.
Appearance - Stations.	- paint hoarding to suit locale. - install landscaping treatment in advance.	Where appropriate. Where construction program and site size permits.
Inconvenience.	- select cable design to suit traffic conditions. - select timing of construction.	Where possible. Where scheduling permits.
Heritage Resources.	- structural and/or locational adjustments. - on and off site landscaping. - install suitable enclosures. - document and remove resource. - relocate electrical facilities.	As required. As required. As required. As required. As required.

Note: The nature of the environment in the study area will determine the potential environmental effects for any project. Mitigation to address these effects will be determined on a case by case basis. Alternatives will be evaluated on the basis of net environmental effects (i.e., environmental effect - mitigation = net environmental effect).